

COUNTY OF HUMBOLDT EXTRACTION REVIEW TEAM (CHERT)

2014 POST-EXTRACTION REPORT

FINAL

Prepared by:

Randy Klein, Doug Jager, Andre Lehre and Bill Trush  
County of Humboldt Extraction Review Team (CHERT)

For the:

Humboldt County Board of Supervisors

Revised June 1, 2015

(revisions made to Tables 3, 4, and 10 and Appendix A. p. 9)

This report is being issued as a  
Final Draft.

Comments submitted during the 60-day public review period of  
April 1 through June 1, 2015 are addressed in this revision,  
and include revisions made to Tables 3, 4, and 10 and Appendix A. p. 9

**TABLE OF CONTENTS**

INTRODUCTION .....2  
Humboldt County Instream Gravel Extraction Sites and Extraction Terminology .....3  
2014 EXTRACTION SUMMARIES .....4  
River Reach Extraction Volumes .....4  
PERFORMANCE ISSUES: 2014 .....7  
APPENDIX A: HISTORICAL EXTRACTION VOLUME SUMMARIES .....9

## INTRODUCTION

This report presents an overview of the Humboldt County gravel extraction for the 2014 season. Information on mining volumes, methods, and success of mine operators in meeting approved plans is reported herein. Representing Humboldt County, the County of Humboldt Extraction Review Team (CHERT) provided site-specific recommendations on extraction designs submitted by the operators and their consultants, as did agencies with regulatory and oversight responsibilities, including: 1) US Army Corps of Engineers (Corps), 2) National Marine Fisheries Service (NMFS), and 3) California Department of Fish and Wildlife (CDFW). Recommendations were based on field reviews at each site, aerial photos, and topographic and hydrologic information provided by the operators as required by the US Army Corps of Engineers 2010 Letter of Permission (LOP) and individual permits obtained by several operators. The 2010 LOP and associated documents are the primary federal instruments regulating gravel mining operations in Humboldt County. LOP 2010 expired in December, 2014. A new LOP is expected to be issued prior to the beginning of the 2015 mining season.

The Humboldt County Board of Supervisors created CHERT in 1992 to provide scientific oversight on Mad River gravel extraction, which had arrived at an impasse over environmental concerns. Four CHERT members were appointed by the Board with expertise in hydrology, fluvial geomorphology, and river ecology; those same four members continue to serve through the present. In 1996, the scope of CHERT services was expanded to include most riverine extraction sites throughout Humboldt County. Additional details on CHERT's role have been presented in earlier post-extraction reports found, along with other County gravel mining documents, at: <http://www.humboldt.gov.org/252/Surface-Mining-Reclamation-Act-SMARA-Doc> .

The annual review process consists of visiting sites in the spring with operators and agency staff to observe post-winter conditions, note undesirable effects from the previous season's extraction (if any), and discuss a possible mining plan for the upcoming extraction season. Later, operators submit air photos, topographic and hydrologic information, and a mining proposal, occasionally followed by a second field review. CHERT then issues a written recommendation, which may suggest changes to reflect either CHERT's or an agency's concerns. Once all parties accept a final iteration of the mining plan, and it is approved by the Corps and CDFW, mining can begin provided all other agency permits have been obtained. In rare occasions, a field review may be done while mining is taking place due to unexpected circumstances that might require alteration to an approved plan. Post-extraction field reviews are conducted after mining is completed in late-summer or fall. Each operator then compiles a post-extraction data set, including pre and post-extraction topographic data, volume calculations, aerial photographs, and other pertinent data. These data are submitted to CHERT, CDFW, Corps, and NMFS.

CHERT develops recommendations based on two primary goals: 1) minimizing potential cumulative effects by ensuring that reach-scale mining volumes do not exceed sustainable levels, and 2) ensuring that site-specific methods of extraction (skimming, trenching, etc.) are appropriate for protecting local habitat. The concept of 'sustained yield' gravel extraction requires that gravel extraction volumes not exceed mean annual recruitment (an estimate of the long-term average annual supply of gravel to a specific reach of a river). Actual mined gravel volumes are typically well below mean annual recruitment. Site-specific measures are also recommended by CHERT to reduce both cumulative and localized potential mining effects on riparian and aquatic habitat. These may include, for example, ensuring that skim floor elevations are sufficiently high to maintain low flow channel confinement so that small rises in river stage do not inundate skim surfaces too readily.

With time, experience on the rivers, and interaction with regulatory agencies, mine operators, and other stakeholders, the measures taken to protect river habitat and to improve program functioning are continually being refined. This feedback process, termed 'adaptive management', helps ensure that gravel mining and management improves resource protection, the quality of information provided by mine operators, and program efficiency. Problems occasionally arise, however, when either the river's response to previous mining results in undesirable river habitat conditions, or an operator deviated from an approved mining plan.

In addition to recurring activities (e.g., mining site reviews, extraction recommendations, annual post-extraction report preparation), CHERT occasionally participates in other activities. For example, CHERT prepared a technical

analysis of Mad River physical channel conditions, riparian vegetation, and fish habitat in 2009 to support physical and biological assessments required for renewal of federal and state permits. Such analyses occur when requested by the County, the operators, or other stakeholders and with direction from the Humboldt County Board of Supervisors.

A new gravel mine site was recently permitted by federal regulatory agencies and extracted gravel from the Mad River for the first time in 2011. The operator of this site, the Blue Lake Rancheria, was not required to obtain permits from the State of California or Humboldt County, and consequently, operates outside of the CHERT program. Their mining plans are reviewed by the US Army Corps of Engineers and National Marine Fisheries Service. They receive no CHERT review, nor do they provide mining information to CHERT, so this report contains no information from the Rancheria’s mining operations. Consequently, the volume of gravel mined from the Mad River since 2011 has been greater than that reported by CHERT.

Although Eel River cross sections (covering mining reaches in the Lower Eel and Van Duzen rivers, the Middle Reach Eel above Scotia, and the South Fork Eel) have been surveyed since about 1997 and have been used in the annual mining review process, a quantitative, longer-term cross section analysis had not been done until early 2009. As part of the renewal of federal and state permits, a multi-year analysis of cross sections was prepared by CHERT to support impact evaluation and refine protection/mitigation strategies. The Eel River cross section report also provides essential information for updating environmental documentation for Eel River gravel mining. As mentioned above, CHERT reports, including the Eel River cross section analysis, can be found at and downloaded from the Humboldt County Planning and Building’s website: <http://www.humboldt.gov/252/Surface-Mining-Reclamation-Act-SMARA-Doc>.

***Humboldt County Instream Gravel Extraction Sites and Extraction Terminology***

Table 1 describes the geographic breakdown of Humboldt County mining reaches. CHERT classifies extraction techniques into twelve descriptive categories in Table 2.

Table 1 - Description of river reaches used to sort and report extraction data.

Approximate Length (miles)	River Reaches
7	<b>Mad River:</b> The Mad River Reach extends approximately seven miles downstream from the Blue Lake Fish Hatchery to just below the Highway 299 Bridge near Arcata.
6	<b>Lower Eel River:</b> The Lower Eel River Reach extends approximately six miles downstream from the mouth of the Van Duzen River to near Fernbridge.
5	<b>Lower Van Duzen River:</b> The Lower Van Duzen River Reach extends upstream approximately five miles from the mouth of the Van Duzen River.
26	<b>Middle Reach of Eel River:</b> The Middle Reach of the Eel River extends upstream from Scotia (River mile 20) for approximately 26 miles to River Mile 46.
17	<b>South Fork Eel River:</b> The South Fork Reach extends from Garberville (River mile 33) upstream to Cooks Valley near the Mendocino County line (River mile 50).
15	<b>Trinity River Reach:</b> The Trinity River Reach extends downstream about 15 miles from near Willow Creek into the Hoopa Valley.
	<b>Isolated Sites:</b> Five extraction sites are more or less isolated from the rest of project. These are the <i>Satterlee Bar</i> on the main stem of the Eel River at Fort Seward, the <i>PL Bar</i> on the Van Duzen River, the <i>Branstetter Bar</i> on Bear River, the <i>Charles Bar</i> on Larabee Creek, and the <i>Cook Bar</i> on the North Fork of the Mattole River.

Table 2. - CHERT extraction methodology terminology and descriptions.

Narrow Shoreline Skim	A skim with one edge close to the low flow channel at or above the 35% flow elevation with a width no greater than 1/3 that of the unvegetated bar surface.
Wide Shoreline Skim	Same as above but wider.
Narrow Offset Skim	A skim that has a substantial vertical or horizontal offset from the low flow channel and a width no greater than 1/3 that of the unvegetated bar surface.
Wide Offset Skim	Same as above, but wider. Some may refer to this as a 'horseshoe' skim.
Dry Trench	A relatively long, linear shallow skim that remains above the water table at the time of excavation.
Wet Trench	A trench sufficiently deep to intersect the water table at the time of excavation, designed for high water to flow through the trench.
Wet Alcove	An excavation designed to simulate naturally occurring shoreline pools, typically located at the downstream ends of naturally occurring scour channels on the backside of meanders, that can provide deep cool water during summer months and/or winter high velocity refuge.
Dry Alcove	Same as above, but to a depth above the water table at the time of excavation.
Fish Access Channel	A channel excavation that may include pools and incorporate large wood designed to temporarily improve fish migration access.
Wetland Pit	A strategically located and designed pit simulating a remnant channel feature, such as an oxbow pond (see Fig. 1); sometimes provided with a small outlet channel.
Terrace Skim	A free-draining skim located on a low terrace above typical high water.
Terrace Pit	A pit excavated on a low terrace with an outlet provided to allow water to freely enter and exit the pit with changes in river stage.

## 2014 EXTRACTION SUMMARIES

### *River Reach Extraction Volumes*

In 2014, CHERT reviewed 34 extraction areas (some multiple times) distributed among 15 mining sites in Humboldt County (many sites had more than one extraction area). Appendix A provides historical gravel extraction volumes from the beginning of the CHERT program in 1992 (Mad River) and the expansion in 1997 (Eel River, Trinity River, and isolated sites added). As shown in Table 3, the total volume of gravel approved for extraction in 2014 was 376,467 cubic yards (cy). The total volume actually extracted was 285,527 cy, or about 76% of that approved for extraction. As mentioned above, any gravel extraction done by Blue Lake Rancheria is not included in this report.

Table 3. Humboldt County 2014 gravel extraction summary by river reach.

River Reach	No. of mined areas	No. of mined sites	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent of Approved Volume	Extracted Area (acres)
Lower Mad River	15	8	69,322	66,743	96%	19.4
Lower Eel River	9	2	127,671	97,232	76%	17.2
Middle Eel River	2	2	59,298	45,394	77%	9.3
Van Duzen River	6	2	74,701	51,404	69%	9.6
South Fork Eel River	2	1	32,341	24,754	77%	4.9
Trinity River	0	0	13,134	0	0%	0.0
Isolated Sites	0	0	0	0	n/a	0.0
<b>Humboldt County Total =</b>	<b>34</b>	<b>15</b>	<b>376,467</b>	<b>285,527</b>	<b>76%</b>	<b>60.4</b>

Tables 4-9 list site-specific 2014 extraction information for each extraction area grouped by river reach. Sites are listed from downstream to upstream in each table. There was no gravel extraction from the Trinity River or isolated sites in 2014.

Table 4. Mad River gravel extractions in the 2014 extraction season. The volumes listed in this table do not include any taken by the Blue Lake Rancheria.

Operator	Sites	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Eureka Ready Mix	O'Neill Bar	1	wide shoreline skim	3,111	3,531	114%	2.5
Miller Family Trust	Miller Bar	n/a	none proposed	0	0	n/a	0.0
Eureka Ready Mix	Johnson-Spini Bar	1	wide shoreline skim	5,870	6,172	105%	4.6
Eureka Ready Mix	Johnson-Spini Bar	2	dry trench	3,015	4,254	141%	0.9
Mercer Fraser Co.	Essex Bar	1	wide shoreline skim	1,880	1,692	90%	0.6
Eureka Ready Mix	Leta-Johnson Bar	1	narrow offset skim	4,638	4,309	93%	1.9
Eureka Ready Mix	Christie Bar	1	terrace skim	15,588	13,881	89%	1.8
Eureka Ready Mix	Christie Bar	2	dry trench	2,208	2,325	105%	0.6
Eureka Ready Mix	Christie Bar	3	dry trench	276	0	0%	0.0
GLJ Construction	Blue Lake Bar	1	narrow shoreline skim	11,722	9,340	80%	2.6
Eureka Ready Mix	Emmerson Bar	1	terrace skim	3,342	3,342	100%	0.7
Eureka Ready Mix	Emmerson Bar	2	terrace skim	2,876	2,876	100%	0.1
Mad River Sand and Gravel	Guynup Bar	3	terrace skim	4,223	4,223	100%	0.2
Mad River Sand and Gravel	Guynup Bar	1	alcove	1,660	3,022	182%	0.2
Mad River Sand and Gravel	Guynup Bar	1	narrow shoreline skim	4,859	4,163	86%	1.1
Mad River Sand and Gravel	Guynup Bar	2	narrow shoreline skim	4,054	3,613	89%	1.6
<b>River Reach Totals =</b>		<b>15</b>	<b>---</b>	<b>69,322</b>	<b>66,743</b>	<b>96%</b>	<b>19.4</b>

Table 5. Lower Eel River gravel extractions in the 2014 extraction season.

Operator	Site	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Eureka Ready Mix	Singley Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
County of Humboldt	Worswick Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Mallard Pond	Drake Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Mercer Fraser Co.	Sandy Prairie: Plant A	A1	dry trench	8,507	6,953	43%	1.4
Mercer Fraser Co.	Sandy Prairie: Plant A	A2	wet trench	14,182	15,567	110%	1.2
Mercer Fraser Co.	Sandy Prairie: Plant A	A3	wet trench	12,130	6,159	51%	0.7
Mercer Fraser Co.	Sandy Prairie: Plant A	A4	narrow skim	16,293	8,609	53%	1.6
Mercer Fraser Co.	Sandy Prairie: Plant A	A5	wet trench	14,308	6,102	43%	0.6
Mercer Fraser Co.	Sandy Prairie: Plant B	B1	narrow skim	2,606	0	0%	0.0
Mercer Fraser Co.	Sandy Prairie: Plant B	B2	narrow skim	13,168	11,156	85%	3.2
Mercer Fraser Co.	Sandy Prairie: Plant B	B3	dry trench	11,721	12,080	103%	3.7
Hansen Truck Shop	Hansen Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Eureka Ready Mix	Hauck Bar	1	wet trench	34,756	30,606	88%	4.8
<b>River Reach Totals =</b>		<b>9</b>	<b>---</b>	<b>127,671</b>	<b>97,232</b>	<b>76%</b>	<b>17.2</b>

Table 6. Middle Eel River gravel extractions, 2014.

Operator	Site	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Humboldt Redwoods Co.	Scotia Dam Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Lower Truck Shop Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Upper Truck Shop Bar	1	wet trench	29,548	18,858	64%	4.0
Humboldt Redwoods Co.	Three Mile Bridge Bar	2	narrow shoreline skim	29,750	26,536	89%	5.3
Humboldt Redwoods Co.	Dinner Creek Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Elinor Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Larabee Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	South Fork Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Bowley Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Maynard Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Humboldt Redwoods Co.	Vroman Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
<b>River Reach Totals =</b>		<b>2</b>	<b>---</b>	<b>59,298</b>	<b>45,394</b>	<b>77%</b>	<b>9.3</b>

Table 7. Van Duzen River gravel extractions, 2014.

Operator	Site	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Leland Rock		1	wet trench	24,912	19,473	78%	2.4
Leland Rock		2	wet trench	31,346	14,476	46%	2.4
Van Duzen River Ranch		n/a	no extraction proposed	n/a	n/a	n/a	n/a
Tom Bess	East Site	1	narrow shoreline skim	3,081	3,300	107%	1.9
Tom Bess	West Site	2	narrow shoreline skim	3,144	2,954	94%	1.0
Tom Bess	West Site	3	narrow shoreline skim	5,055	4,294	85%	1.4
Tom Bess	West Site	4	wet trench	7,163	6,907	96%	0.5
<b>River Reach Totals =</b>		<b>6</b>	<b>---</b>	<b>74,701</b>	<b>51,404</b>	<b>69%</b>	<b>9.6</b>

Table 8. South Fork Eel River gravel extractions, 2014.

Operator	Site	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Wallan and Johnson	Wallan and Johnson Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Randall Sand and Gravel	Home Bar	1	wide shoreline skim	18,174	13,154	72%	2.7
Randall Sand and Gravel	Home Bar	2	wide shoreline skim	14,167	11,600	82%	2.2
Mercer Fraser Co.	Cooks Valley: MEN *	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Mercer Fraser Co.	Cooks Valley: HUM *	n/a	no extraction proposed	n/a	n/a	n/a	n/a
<b>River Reach Totals =</b>		<b>2</b>	<b>---</b>	<b>32,341</b>	<b>24,754</b>	<b>77%</b>	<b>4.9</b>

\* "HUM" is in Humboldt County, "MEN" is in Mendocino County

Table 9. Trinity River gravel extractions, 2014.

Operator	Sites	Area No.	Method	Approved Volume (cu. yds.)	Extracted Volume (cu. yds.)	Percent of Approved Volume	Extracted Area (acres)
Mercer Fraser Co.	Willow Creek Site	1	wide offset skim	8,896	0	0%	0.0
Mercer Fraser Co.	Willow Creek Site	2	wide shoreline skim	4,238	0	0%	0.0
Mercer Fraser Co.	McKnight Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
Klamath Trinity Aggregates	Rowland Bar	n/a	no extraction proposed	n/a	n/a	n/a	n/a
<b>River Reach Totals =</b>		<b>2</b>	<b>---</b>	<b>13,134</b>	<b>0</b>	<b>0%</b>	<b>0.0</b>

Humboldt County extraction volumes and surface areas by method for 2014 are shown in Table 10.

Table 10. Humboldt County gravel extraction volumes and areas by mining method, 2014.

Extraction Method	No. of Areas	Extracted Volume (cy)	Percent of total volume	Area (acres)	Percent of total area
dry trench	4	25,612	9%	6.6	11%
narrow offset skim	2	12,918	5%	3.5	6%
narrow shoreline skim	8	65,356	23%	18.1	30%
terrace skim	4	24,322	9%	2.8	5%
wet alcove	1	3,022	1%	0.2	0%
wet trench	8	118,148	41%	16.6	27%
wide shoreline skim	5	36,149	13%	12.6	21%
<b>Humboldt County Totals =</b>	<b>32</b>	<b>285,527</b>	<b>100%</b>	<b>60.4</b>	<b>100%</b>

## PERFORMANCE ISSUES: 2014

To evaluate operator performance and compliance, CHERT and regulatory agency staff conduct field reviews in the fall after completion of operations and reviews post-extraction documentation (cross sections, air photos, and other materials) to ensure approved mining plan design specifications were met. By and large, operator performance in conducting their 2014 operations consistent with approved mining plans was very successful. Although most extractions were below their approved volumes, several sites exceeded approved volumes, but only by minor amounts.

At several mined areas, the actual extraction volume was much less than that approved. This does not present a problem as long as the area is left in a condition that meets design objectives (the area will drain effectively after inundation by river flows and so does not have depressions that may trap fish). One area exhibited non-free draining condition in 2014 (see below).

In late October, 2014, rains occurred while some operations were still being extracted, with two such operations observed by the CDFW to have heavy equipment working in the wetted channel. Any regulatory processes that may ensue will be undertaken by the CDFW and possibly other agencies. In fact, most of the notes below were copied and/or paraphrased from a CDFW memo. We note again that CHERT has no regulatory authority, but coordinates with the regulatory agencies on deviations from approved plans and remedial actions.

### Problems noted in 2014:

- A dry trench at the Johnson-Spini site, Mad River, appeared to have been over-extracted by digging too deep (see Table 4). However, field discussions during development of the approved plan specified that the trench bottom be above the saturated substrate, and the operator complied with this. The apparent over-

extraction was due to the unknown depth to saturated substrate at the time of plan preparation, thus the operator was in compliance with the approved plan.

- At the Mad River Sand and Gravel site, Mad River, over-extraction occurred at the alcove (Area 1, see Table 4). This resulted from portions of the alcove being dug too wide and/or deep. We note the difficulty in precise extraction from wet trenches because of the tendency for trench walls to collapse inward during extraction.
- On October 10, 2014, at the Upper Truck Shop gravel bar (Humboldt Redwoods Corp. site, Middle Eel River) CDFW observed that trenching was being conducted with the excavator immersed in the wetted channel in the process of loading dump trucks. CDFW discussed with HRC staff onsite and the activity was discontinued. In addition, a small, dry tributary stream at base of access road was not adequately day-lighted. Corrective measures were discussed and implemented before the onset of rain.
- At the Leland Rock site (Van Duzen River delta), CDFW observed on October 10, 2014, that the bridge span over a secondary channel at the Leland Rock site was set too low to accommodate potential late season river rises and was not oriented perpendicular to the river as required. Also, as in prior years, vehicle safety berms were used rather than re-contouring extraction area boundaries by laying back slopes. The importance of this was re-emphasized to the operator.
- On October 23, 2014, extraction activities at the Sandy Prairie site (Mercer Fraser Co., Lower Eel River) were observed by CDFW being conducted under saturated conditions during a significant rain and river rise event with turbid water discharges and inundation of haul roads, bridge abutments and approaches. Bridge removal with heavy equipment was occurring in the active channel while salmon were migrating. From October 20 through 22, 2014, based on NOAA prediction of rain and river rise, CDFW requested that the operator remove their seasonal bridge by October 22 in emails and phone calls. These communication attempts went unanswered. On October 24, 2014, CDFW requested that fill in channel be removed and the access road be water-barred to prevent fill discharge and turbid water road surface runoff from entering the river. On the post-extraction review it appeared this had not taken place.
- Also at the post-extraction review at the Sandy Prairie site (Mercer Fraser Co., Lower Eel River) CDFW observed at Area A1 that an approximately 0.5 acre thicket of a narrow-leaved willow (*Salix exigua*) had been uprooted and/or crushed from gravel stockpiling, loading, and hauling activities. Other scattered damage to narrow-leaved willow was also observed in other gravel extraction areas at the site. Additionally, Area A1 was not extracted at the approved location (farther off-set from secondary channel).
- At the Sandy Prairie site (Mercer Fraser Co., Lower Eel River) post-extraction site review, it was observed that Area A4 was not extracted at the approved location. Instead, it was positioned farther from the adjacent channel. As a result, the extraction area was not left in a free-draining condition and had potential to trap outgoing salmonids during spring flows. Area A4 will need to be monitored for fish entrapment as long as it remains in this condition.

## APPENDIX A: HISTORICAL EXTRACTION VOLUME SUMMARIES

Humboldt County Totals ("---" means unknown)				Mad River ("---" means unknown)			
Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent	Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent
1992	---	---	---	1992	115,000	115,000	100%
1993	---	---	---	1993	122,100	138,400	113%
1994	---	---	---	1994	134,500	134,898	100%
1995	---	---	---	1995	210,637	226,265	107%
1996	---	---	---	1996	203,998	189,517	93%
1997	---	---	---	1997	252,926	210,976	83%
1998	1,075,095	820,952	76%	1998	265,795	223,352	84%
1999	1,142,212	860,974	75%	1999	196,212	174,974	89%
2000	987,848	706,234	71%	2000	204,748	146,534	72%
2001	979,515	494,819	51%	2001	199,215	167,719	84%
2002	1,023,866	748,461	73%	2002	204,991	171,937	84%
2003	881,090	581,800	66%	2003	150,390	136,790	91%
2004	692,020	440,710	64%	2004	156,540	141,250	90%
2005	664,565	493,240	74%	2005	138,475	127,200	92%
2006	700,660	561,845	80%	2006	174,245	162,360	93%
2007	784,108	612,132	78%	2007	165,504	153,341	93%
2008	659,022	534,821	81%	2008	142,043	130,613	92%
2009	454,213	211,207	46%	2009	0	0	n/a
2010	562,303	374,313	67%	2010	111,439	86,246	77%
2011	774,582	505,805	65%	2011	147,380	143,124	97%
2012	553,704	384,514	69%	2012	111,317	100,329	90%
2013	362,222	226,362	62%	2013	80,525	76,919	96%
2014	376,467	285,527	76%	2014	69,322	66,743	96%
<b>Totals</b>	<b>12,673,492</b>	<b>8,843,716</b>	<b>70%</b>	<b>Totals</b>	<b>3,557,302</b>	<b>3,224,487</b>	<b>91%</b>
<b>Averages</b>	<b>745,500</b>	<b>520,219</b>	<b>70%</b>	<b>Averages</b>	<b>154,665</b>	<b>140,195</b>	<b>91%</b>

## APPENDIX A (continued)

Lower Eel River ("---" means unknown)				Middle Eel River ("---" means unknown)			
Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent	Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent
1992	---	---	---	1992	---	---	---
1993	---	---	---	1993	---	---	---
1994	---	---	---	1994	---	---	---
1995	---	---	---	1995	---	---	---
1996	---	---	---	1996	---	---	---
1997	561,700	326,500	58%	1997	147,300	84,900	58%
1998	399,100	273,000	68%	1998	157,900	99,400	63%
1999	471,400	290,500	62%	1999	134,900	124,900	93%
2000	291,300	208,600	72%	2000	160,100	131,000	82%
2001	389,900	119,300	31%	2001	116,100	64,000	55%
2002	387,300	220,000	57%	2002	132,767	121,608	92%
2003	318,300	163,900	51%	2003	74,030	54,060	73%
2004	188,840	120,305	64%	2004	0	0	n/a
2005	199,370	166,280	83%	2005	0	0	n/a
2006	235,495	208,240	88%	2006	0	0	n/a
2007	243,097	177,334	73%	2007	89,990	64,424	72%
2008	237,955	215,760	91%	2008	0	0	n/a
2009	229,386	106,467	46%	2009	0	0	n/a
2010	208,286	188,730	91%	2010	0	0	n/a
2011	301,537	214,730	71%	2011	76,715	35,618	46%
2012	226,520	188,994	83%	2012	29,569	25,880	88%
2013	176,477	80,918	46%	2013	0	0	n/a
2014	127,671	97,232	76%	2014	59,298	45,394	77%
<b>Totals</b>	<b>5,193,634</b>	<b>3,366,790</b>	<b>65%</b>	<b>Totals</b>	<b>1,178,669</b>	<b>851,184</b>	<b>72%</b>
<b>Averages</b>	<b>288,535</b>	<b>187,044</b>	<b>65%</b>	<b>Averages</b>	<b>65,482</b>	<b>47,288</b>	<b>72%</b>

## APPENDIX A (continued)

South Fork Eel River ("---" means unknown)				Van Duzen River ("---" means unknown)			
Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent	Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent
1992	---	---	---	1992	---	---	---
1993	---	---	---	1993	---	---	---
1994	---	---	---	1994	---	---	---
1995	---	---	---	1995	---	---	---
1996	---	---	---	1996	---	---	---
1997	67,700	74,700	110%	1997	120,000	81,600	68%
1998	75,400	70,100	93%	1998	119,100	103,700	87%
1999	85,400	75,900	89%	1999	159,900	108,800	68%
2000	75,700	53,700	71%	2000	194,800	121,300	62%
2001	66,000	43,100	65%	2001	161,700	85,600	53%
2002	58,163	48,122	83%	2002	202,500	167,400	83%
2003	87,060	54,660	63%	2003	175,100	123,000	70%
2004	80,730	50,745	63%	2004	179,045	92,610	52%
2005	82,770	36,480	44%	2005	159,090	123,170	77%
2006	92,000	35,075	38%	2006	134,910	104,750	78%
2007	90,737	73,956	82%	2007	152,773	113,184	74%
2008	32,358	24,833	77%	2008	209,176	137,850	66%
2009	40,170	24,986	62%	2009	175,132	73,236	42%
2010	42,864	27,732	65%	2010	169,041	69,917	41%
2011	36,063	14,244	39%	2011	175,724	71,903	41%
2012	19,039	0	0%	2012	142,191	47,760	34%
2013	27,588	17,212	62%	2013	63,111	41,713	66%
2014	32,341	24,754	77%	2014	74,701	51,404	69%
<b>Totals</b>	<b>1,092,083</b>	<b>750,299</b>	<b>69%</b>	<b>Totals</b>	<b>2,767,994</b>	<b>1,718,897</b>	<b>62%</b>
<b>Averages</b>	<b>60,671</b>	<b>41,683</b>	<b>69%</b>	<b>Averages</b>	<b>153,777</b>	<b>95,494</b>	<b>62%</b>

## APPENDIX A (continued)

Trinity River ("---" means unknown)				Isolated Sites ("---" means unknown)			
Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent	Year	Approved Volume (cubic yards)	Extracted Volume (cubic yards)	Percent
1992	---	---	---	1992	---	---	---
1993	---	---	---	1993	---	---	---
1994	---	---	---	1994	---	---	---
1995	---	---	---	1995	---	---	---
1996	---	---	---	1996	---	---	---
1997	47,500	40,000	84%	1997	---	---	---
1998	35,000	28,100	80%	1998	22,800	23,300	102%
1999	64,300	66,900	104%	1999	30,100	19,000	63%
2000	18,000	22,200	123%	2000	43,200	22,900	53%
2001	46,600	15,100	32%	2001	0	0	n/a
2002	38,145	19,394	51%	2002	0	0	n/a
2003	76,210	49,390	65%	2003	0	0	n/a
2004	62,075	32,700	53%	2004	24,790	3,100	13%
2005	64,100	30,570	48%	2005	20,760	9,540	46%
2006	64,010	51,420	80%	2006	0	0	n/a
2007	42,007	29,893	71%	2007	0	0	n/a
2008	12,490	11,701	94%	2008	25,000	14,064	56%
2009	0	0	n/a	2009	9,525	6,518	68%
2010	30,673	1,688	6%	2010	0	0	n/a
2011	37,163	26,186	70%	2011	0	0	n/a
2012	25,068	21,551	86%	2012	0	0	n/a
2013	5,521	723	13%	2013	0	0	n/a
2014	13,134	0	0%	2014	0	0	n/a
<b>Totals</b>	<b>681,996</b>	<b>447,516</b>	<b>66%</b>	<b>Totals</b>	<b>176,175</b>	<b>98,422</b>	<b>56%</b>
<b>Averages</b>	<b>37,889</b>	<b>24,862</b>	<b>66%</b>	<b>Averages</b>	<b>10,363</b>	<b>5,790</b>	<b>56%</b>